



# The Daya Bay Reactor Neutrino Experiment

Jonathan Link

Virginia Polytechnic Institute & State University  
on behalf of the Daya Bay Collaboration

Neutrino Champagne 2009

October 19, 2009





# The Daya Bay Nuclear Power Plant


Located in Guangdong Province, China about 1 hour from Hong Kong

4 Reactors with 11.6 GW thermal power going to 6 reactor with 17.4 GW<sub>th</sub> in early 2011

Among the most powerful NPP in the world

Mountainous terrain is well suited for shielding underground detectors

The utility company (China Guangdong Nuclear Power Group) has joined the collaboration





# Daya Bay Design Principles

Identical near and far detectors cancel many systematic error.

Multiple modules boost statistics while reducing systematic errors with multiple independent measurements and direct comparisons of detector counting rates in a common  $\nu$  flux.

Three zone detector design eliminates the need for spatial cuts which can introduce systematic uncertainties.

Shielding from cosmic rays and natural radioactivity reduces background rates and provides measurable handles on remaining background.

Movable detectors allows for concurrent civil and detector construction, early detector commissioning at the near site, and possible cross calibration between near and far detectors to further reduce systematic errors.

2009/09/24 09:59



# Experimental Setup

Total tunnel length ~ 3000 m

Far site  
Overburden: 355 m

**Empty** detectors: moved to underground halls via access tunnel.  
**Filled** detectors: transported between halls via horizontal tunnels.

Ling Ao Near  
Overburden: 112 m

Ling Ao II  
Reactors  
(Starting 2011)

Ling Ao  
Reactors

Daya Bay  
Reactors

Daya Bay Near  
Overburden: 98 m

Entrance

Water  
hall

Liquid  
Scintillator  
hall


Construction  
tunnel

u 006

465 m

810 m

295 m





# Experimental Setup

- 8 identical **anti-neutrino detectors** ( two at each near site and four at the far site) to cross-check detector efficiency
- Two near sites sample flux from reactor groups

9 different baselines under the assumption of point size reactor cores and detectors

**Far site**  
Overburden: 355 m

**Ling Ao Near**  
Overburden: 112 m

**Ling Ao II  
Reactors  
(Starting 2011)**

**Ling Ao  
Reactors**


**Daya Bay Near**  
Overburden: 98 m

**Daya Bay  
Reactors**

Halls Reactors \	Daya Bay Near (m)	Ling Ao Near (m)	Far (m)
Daya Bay	363	1347	1985
Ling Ao I	857	481	1618
Ling Ao II	1307	526	1613



# The Daya Bay Detector Design



There are 8 antineutrino detectors in all

Three zone, cylindrical design

- 0.1% wt Gd-Loaded LS target

- LS gamma catcher

- Mineral oil buffer

Reflectors at top and bottom

196 PMT's arrayed around the barrel of the cylinder

5 meter total diameter

Designed to sit in a pool of ultrapure water

For more information on the liquid scintillator see the poster by Qi Ming



# Water Shield and Muon Tagging System

The water pool shields the detectors from energetic  $\gamma$ -rays from the decay chains of  $^{238}\text{U}$ ,  $^{232}\text{Th}$  and  $^{40}\text{K}$  in surrounding the rock


It also detects the Čerenkov light produced by cosmic ray muons which pass near the detectors

The pool is lined with white Tyvek and sparsely populated with PMTs

The pool is optically separated into two zones (inner and outer)

The top is covered with 4 layers of RPC

The two zones allow a better measurement of efficiency




Minimum 2.5 m water shielding in all directions.



# Measuring $\sin^2 2\theta_{13}$

The measurement is ultimately a ratio of observed inverse  $\beta$ -decay events in near and far detectors in initially one, but ultimately many energy bins (sampling a broad range of oscillation phases).

$$\frac{N_f}{N_n}$$



Proton  
Number  
Ratio



$\pm 0.3\%$



$\sin^2 2\theta_{13}$



# Controlling the Proton Ratio Systematic Error


The final step in building the detectors is to fill the three zones.

Detectors are filled underground.

Detectors will be filled in pairs (one far, one near) from common scintillator and mineral oil batches.

Mixed fluid weights are carefully measured throughout the filling.

As are fluid flow rates.



Gd-LS weighing tank

Filling Platform with Clean Room

Pump Stations

Detector

Load Cells

Coriolis mass flowmeters  
< 0.1%

For food, beverage, pharmaceutical and chemical applications!

Teflon-lined ISO The antineutrino detector filling hall accuracy < 0.02%



# Measuring $\sin^2 2\theta_{13}$

The measurement is ultimately a ratio of observed inverse  $\beta$ -decay events in near and far detectors in initially one, but ultimately many energy bins (sampling a broad range of oscillation phases).

$$\frac{N_f}{N_n} = \left( \frac{N_{p,f}}{N_{p,n}} \right) \left( \frac{L_n}{L_f} \right)^2 \left[ \frac{P_{ee}(E, L_f)}{P_{ee}(E, L_n)} \right]$$

Proton  
Number  
Ratio



$\pm 0.3\%$

Ratio of  
Detector  
Efficiencies



Calibration  $\rightarrow \pm 0.2\%$

$\sin^2 2\theta_{13}$




# Calibration System

Automated calibration system with routine weekly deployment of sources

LED light sources for monitoring optical properties

Stopped  $e^+$  and  $n$  sources give fixed energies for energy calibration

- $^{68}\text{Ge}$  source
- $\text{Am-}^{13}\text{C} + ^{60}\text{Co}$  source
- LED diffuser ball




Calibration units which remotely insert a range of calibration devices along a vertical axis in each of the three zones.




# Efficiency and Energy Calibrations

## Prompt Energy Signal



## Delayed Energy Signal



Stopped positron signal from the  $^{68}\text{Ge}$  source ( $2 \times 0.511 \text{ MeV}$ ) gives us the inverse  $\beta$ -decay positron energy threshold

Neutrons ( $\text{Am-}^{13}\text{C}$  and tagged spallation) gives us a 2.2 MeV signal (in the positron energy range) and 8 MeV from Gd neutron capture

*With a 1 MeV cut for prompt positrons:  
>99% efficiency with negligible uncertainty*


*With a 6 MeV cut for delayed neutrons:  
~78% efficiency with 0.22% relative uncertainty*



# Backgrounds

Fast neutron — fast neutron enters detector, creates prompt signal, thermalizes, and is captured.

Correlated decays —  $\beta+n$  decays of  ${}^9\text{Li}$  and  ${}^8\text{He}$  produced in the antineutrino detector by spallation of  $\mu$  on  ${}^{12}\text{C}$ .




Random coincidence — two unrelated events that happen close together in space and time.

Portal to the underground halls which provide from 250 to 925 meters water equivalent shielding



# Signal to Background



After all filters the background rates are small compared to a disappearance due to oscillations with  $\sin^2 2\theta_{13}$  of 1%.

In addition, each background has a characteristic and distinct energy spectrum.

	DYB site	LA site	far site
(a) Antineutrino rate (/day/module)	840	740	90
Natural radiation (singles) (Hz)	<50	<50	<50
Single neutron (/day/module)	18	12	1.5
$\beta$ -emission isotopes (/day/module)	210	141	14.6
(d) Accidental/Signal	<0.2%	<0.2%	<0.1%
(c) Fast neutron/Signal	0.1%	0.1%	0.1%
(b) $^8\text{He}^9\text{Li}$ /Signal	0.3%	0.2%	0.2%






# Systematic and Statistical Errors

Source of Uncertainty		Chooz	Daya Bay ( <i>relative</i> )		
		( <i>absolute</i> )	Baseline	Goal	Goal w/Swapping
Number of Protons		0.8%	0.3%	0.1%	0.006%
Detector Efficiency	Energy Cuts	0.8%	0.2%	0.1%	0.1%
	Position Cuts	0.32%	0.0%	0.0%	0.0%
	Time Cuts	0.4%	0.1%	0.03%	0.03%
	H/Gd Ratio	1.0%	0.1%	0.1%	0.0%
	N Multiplicity	0.5%	0.05%	0.05%	0.05%
	Trigger	0%	0.01%	0.01%	0.01%
	Live Time	0%	<0.01%	<0.01%	<0.01%
Total Detector Related Uncertainty		1.7%	0.38%	0.18%	0.12%
Background (per detector)		0.85%	<0.4%	<0.4%	<0.4%
Neutrino Flux		2.7%	0.13%	0.13%	0.13%
Signal Statistics		1.8%	0.2%	0.2%	0.2%
Sensitivity to $\sin^2 2\theta_{13}$ (at 90% CL)		~13%	0.8%	0.7%	0.6%




# Sensitivity





# Status: Civil Construction

Daya Bay Near Hall  
(100 m underground)



Surface Assembly Building



Control Room/Office Space



Tunnel lining





# Status: Civil Construction

As of late September...

Far site

u 006

Ling Ao Near

465 m

Water  
hall

Construction  
tunnel

Liquid  
Scintillator  
hall

810 m

Ling Ao  
Reactors


Ling Ao II  
Reactors

Entrance

295 m

Daya Bay Near

Daya Bay  
Reactors





# Status: Experimental Components



Stainless Steel Vessel



Detector Transporter



4 m Acrylic Vessel



# Status: Detector Assembly


Delivery of 4 m Acrylic Vessel




SS Tank Delivery




AD Assembly  
Clean Room



Assembly of AD Showing  
Installation of Bottom Reflector



Stainless Steel Tank  
in Assembly Pit





# Project Schedule

- October 2007: Ground Breaking
- Spring 2008: CD3 review completed
- March 2009: Surface Assembly Building occupancy
- Summer 2010: Daya Bay Near Hall ready for data taking
- Summer 2011: All near and far halls ready for data taking

Three years of data taking to reach sensitivity goal.



# The Daya Bay Collaboration

